

# Capital Area Transportation Authority



## AMENDMENT NO. 1 TO SOLICITATION MMG Art Sculpture Foundation Installation

1. AMENDMENT NO:  1	2. SOLICITATION NO:  RFQ 2017-148	3. SOLICITATION NAME: MMG Art Sculpture Foundation Installation	4. AMENDMENT DATE:  November 15, 2017
---------------------------	---	---	---

5. ISSUED BY

Capital Area Transportation Authority  
Purchasing and Contracts Department  
4615 Tranter Street  
Lansing, MI 48910

**PLEASE NOTE: Contractor is required to sign this document and return it with the bid/proposal/quote.**

6. DESCRIPTION OF AMENDMENT:

- a. Exhibit A, Scope of Work has been amended to include the following (please see attached):  
  
“The Contractor will supply the anchor bolts & washers. We will be using the HIT-HY200+HIT-Z-HILTI ADHESIVE ANCHORS ¾” X 6” in 316 stainless steel.”
- b. Attached is a site plan with a rough estimation of where the work will be completed.
- c. All other terms and conditions remain unchanged.

NAME / TITLE OF OFFEROR (Type or Print)	COMPANY NAME
(Signature of person authorized to sign)	(Date Signed)

## EXHIBIT A SCOPE OF WORK

---

Objective:

CATA is requesting prices for Installation of Foundation for Art Sculpture as described below:

- The work covered by these specifications consists of furnishing all labor, equipment and materials to perform all operations in connection with the construction of cement pads and foundations.
- All work must conform to all state and local construction regulations. The contractor will be responsible for obtaining and paying for all required permits. The contractor will be responsible for coordinating and scheduling all work with CATA Staff, Miss Dig and local jurisdictions.
- Work shall commence within two weeks after award of the contract and proceed in an expeditious manner until complete. Contractor shall submit a detailed construction schedule within this two week period as well.
- Contractor assumes full responsibility for protection and safekeeping of materials and equipment on-site.
- Remove and dispose of all brush, rubbish and other debris existing in those areas affected by proposed site modifications and new site development. In areas of new construction, new grading and other site development, and where topsoil is to be removed, should be scraped clean of all brush, weeds, grass, roots and other loose material. Properly dispose of all debris, asphalt and other material from clearing and grubbing off-site.
- Barricades must be placed around each excavation and concrete pour. Site must be made safe and hazard free at all times until the work is completed. The contractor shall be responsible for, and the repair of any vandalism that may occur to the pad while the cement is still wet.
- Contractor is responsible for any traffic warning and road signs required to perform this work. This cost and all other cost must be included in their bid.
- If existing appurtenances or utilities are found to interfere with the permanent facilities being constructed, the Contractor shall immediately notify CATA's Facilities Superintendent.
- Concrete shall have unit weight of 145PCF and a minimum compressive strength (f'c) at 28 days of 4500 PSI
- Maximum water/cement ratio =0.45.
- Entrain air (6%+/- 1.5%) for concrete exposed to freezing temperatures.
- No calcium chloride shall be used in any concrete.
- Mixing, transporting and placing of concrete shall conform to ACI-301, latest addition.
- All concrete work shall conform to the requirements of ACI-318, "Building code requirements for reinforced concrete".
- Chamfer all exposed external corners of concrete with 3/4" X 45 degree chamfer, unless noted otherwise.
- Concrete reinforcement bars shall be deformed and conform to ASTM A615, grade 60. Reinforcing shall not be tack welded, welded, heated or cut, unless indicated on the contract documents. All laps shall be tension spliced unless noted otherwise.
- No foundation or slabs shall be poured into or against subgrade containing free water, frost, ice, or loose material.
- The Contractor will supply the anchor bolts & washers. We will be using the HIT-HY200+HIT-Z-HILTI ADHESIVE ANCHORS 3/4" X 6" in 316 stainless steel.

Contract Details:

- a) The Vendor to supply itemization of all charges, such as Hourly Rate, Overtime (including Double Time), Trip Charges, Truck Charges, Gas Surcharges, and/or any other charges that could be invoiced.
- b) The Contractor will contact Barry Flowers, CATA Project Manager prior to commencement of any work.

Location:

CATA Multi-Modal Gateway, 1240 South Harrison Road, East Lansing

**END OF SECTION**

